13(3) MPSDC/RFP/26/319

Date. 05/03/2026

मध्य प्रदेश राज्य दंत परिषद
Madhya Pradesh State Dental Council
(statutory body of Govt. Of M.P.)

REQUEST FOR PROPOSAL (RFP)

for

"INTERIOR CUM RENOVATION AGENCIES FOR DESIGN EXECUTION AND RENOVATION WORKS AT INDORE"

(All the pages of this NIQ are to be signed in ink by the authorized signatory with official stamp on each page and are to be submitted in original along with the quotation)

MADHYA PRADESH STATE DENTAL COUNCIL
101 – First Floor, Royal House, Near Bright School, Usha Ganj Main Road, Jaora Compound, Indore – 452001

05/03/2026.

REGISTRAR
M.P. STATE DENTAL COUNCIL
INDORE (M.P.)

INDEX

S.No	Details	Page No
01	Information to the Agencies	
02	Brief scope of work	
03	Eligibility Criteria and other details	
04	Other Terms & Conditions	
05	Evaluation of Proposals	
06	Evaluation Criteria for the Proposals	
07	Proforma for Application	
08	Acceptance Letter	
09	Agency Detail's Form	
10	Similar Work Experience (Annexure-I)	
11	Agency Technical Manpower Details (Annexure-II)	
12	Proforma for Annual Turnover (Annexure-III)	
13	Check List for Agency	

The Agencies are requested to enclose an Index Table on first page of the proposal along with enclosures giving details about - Sl. No., Particulars, and Page Nos. from-to, so that during scrutiny of the documents no document is left overlooked by the Institute.

1. Information to the Agencies:

The Madhya Pradesh State Dental Council is a premier statutory body dedicated to regulating the dental profession, ensuring the highest standards of dental education, and maintaining ethical clinical practices across the state. The Council integrates regulatory oversight, professional development and administrative excellence to serve both dental practitioners and the public.

The Council invites proposals from interested, eligible, reputed, and well established interior renovation agencies who have adequate experience in the interior renovation of (i) office receptions, executive cabins, and board rooms of large corporate, government, or academic institutions for carrying out the work **"Interior Fit-Out and Renovation of the President Cabin, Registrar Cabin, Main Reception, and Administrative Areas for the Madhya Pradesh State Dental Council".**

There are 2 stages for the selection proves: (i) **Stage I** – Selection of the agency (ies) on the basis of Technical evaluation. (ii) **Stage II** – Shortlisted agencies are required to prepare and submit a Bill of Quantity (BOQ) and Commercials along with EMD.

The selection of the agency will be based on a site visit to verify the works executed by the bidder & reference checks. It may please be noted that the "Final selection of the agency (ies) for issue of Letter of Award shall be on completion of Stage II" only. The following is the important information for the participating agencies:-

S. No.	Information	Details
01	Work Requirement	Renovation Work of – 1. President Cabin 2. Vice-President Cabin 3. Registrar Cubicles x2 4. Reception/Waiting area 5. Pantry 6. Toilet
02	Date of Publishing of RFP	
03	Pre-submission of proposals meeting of participating agencies at MPSDC, Indore.	
04	Date and Time of closing of proposals	
05	Period of work completion	4 months from the date of issue of Letter of Award (LOA)

The RFP document can be downloaded from the MPSDC website www.mpstatedentalcouncil.com. The duly filled quotation in original along with all requisite documents enclosed duly signed by the authorized person on official stamp on each page should be sealed in an envelope and submitted in the TENDER BOX placed at Institutional Department. Quotations received through e-mail/online will not be considered and summarily rejected.

Agencies should read the document carefully before submission of quotation documents at MPSDC, Indore. The participating agency may please note that MPSDC, Indore at its discretion may cancel any/all proposals received without assigning any reason, at any point of time.

2. Brief scope of work

S. No.	Work	Experience of Agencies to Participate
1	Demolition of Existing walls and re plastering and wall repairing of existing interior space.	Experienced interior design-cum-renovation agencies specializing in office renovation work and boardrooms.
2	Removing and scraping out existing tiles of the space.	Experienced interior design-cum-renovation agencies specializing in office renovation work and boardrooms.
3	Removing existing windows and Reinstalling the new Aluminum, two track windows.	Experienced interior design-cum-renovation agencies specializing in office renovation work and boardrooms.
4	Scraping out uneven walls and preparing it for final finishing	Experienced interior design-cum-renovation agencies specializing in office renovation work and boardrooms.
5	**Conducting & Wiring:** Supply and installation of concealed/surface PVC conduits, laying of wires, and circuiting from the main Distribution Board (DB) to individual switchboards and equipment points. **DB & Protection:** Supply, installation, and termination of the main DB, including MCB's (Miniature Circuit Breakers), RCCBs (Residual Current Circuit Breakers), and isolators. **Fixtures & Fittings:** Installation of all modular switches, sockets, floor boxes, and	Experienced interior design-cum-renovation agencies specializing in office renovation work and boardrooms.

	lighting fixtures (recessed, surface, and profile lights) as per the architectural Reflected Ceiling Plan (RCP). **Testing & Commissioning:** Megger testing of all circuits, load balancing, and final commissioning of the entire electrical system before and over.	
06	**Proposed Material Specifications (To be approved by Architect)** **Wires & Cables:** FRLS (Fire Retardant Low Smoke) copper wires (Suggested makes: Polycab, Finolex, or Havells). **Modular Switches & Sockets:** Premium modular plates and mechanisms (Suggested makes: Legrand , Schneider Electric, Western). **PVC Conduits:** Heavy-duty rigid PVC conduits (Suggested makes: VIP, BEC, or Precision). **MCB/RCCB & Distribution Boards:** (Suggested makes: Legrand, Schneider, or Hager). **Data Cables:** CAT 6 cables for IT networking (Suggested makes: D-Link or AMP).	Experienced interior design–cum–renovation agencies specializing in office renovation work and boardrooms.
07	**Low Voltage (IT, Security & Access Control)** • **Networking:** Laying of CAT 6 cables from the main server/IT rack to all workstations (President, Registrar, Cubicles, Reception). • **CCTV: C**oncealed conduiting and wiring for CCTV cameras covering the Waiting Area, Reception, and main passage.	Experienced interior design–cum–renovation agencies specializing in office renovation work and boardrooms.
08	**Plumbing & Sanitary Scope of Work** **Piping & Routing:** Chasing, core cutting, and laying of concealed/surface water supply lines (hot and cold) and drainage lines (soil, waste, and vent) connecting to the base building's main plumbing shafts. **Waterproofing:** Application of a	Experienced interior design–cum–renovation agencies specializing in office renovation work and boardrooms.

	comprehensive waterproofing system (base coat and protective screed) for the Washroom and Pantry floors before laying tiles, including a water ponding test for a minimum of 72 hours to ensure zero leakage. **Fixture Installation:** Supply, assembly, and installation of all sanitaryware (WC, washbasins) and CP (Chrome Plated) fittings (faucets, health faucets, angle valves, bottle traps). **Testing & Commissioning:** Hydraulic pressure testing of all internal water supply lines to check for leaks, and flow testing of all drainage lines prior to sealing shafts and closing flooring/walls.	
09	**Proposed Material Specifications (To be approved by Architect)** **Internal Water Supply (Hot & Cold):** CPVC (Chlorinated Polyvinyl Chloride) pipes and fittings. (Suggested makes: Ashirvad, Astral, or Supreme). **Drainage & Sewerage:** UPVC / SWR (Soil, Waste, and Rainwater) pipes and fittings with proper slope maintenance. *(Suggested makes: Supreme, Prince, or Astral)*. **Sanitaryware:** Premium ceramic fixtures, including wall-hung WCs with concealed cisterns and washbasins. *(Suggested makes: Jaquar, Hindware, Kohler, or Parryware)*. **CP Fittings:** Premium brass chrome-plated fittings. *(Suggested makes: Jaquar, Kohler, or Grohe)*. **Waterproofing Compounds:** High-quality liquid-applied or cementitious waterproofing membranes. *(Suggested makes: Dr. Fixit, Fosroc, or Pidilite)*.	Experienced interior design–cum–renovation agencies specializing in office renovation work and boardrooms.
10	**General Scope of Work** • **Surface Preparation:** Cleaning, chipping, and leveling the existing base floor to ensure a properly sloped or completely flat substrate (zero-level) prior to installation. • **Layout & Dry Run:** Submitting a shop drawing or physical dry-run	Experienced interior design–cum–renovation agencies specializing in office renovation work and boardrooms.

	layout for the Architect's approval to ensure symmetrical joints, proper alignment with the main entrance, and minimization of awkward tile cuts at the edges. • **Installation:** Supply and laying of 2'x2' (600mm x 600mm) premium vitrified tiles using the approved adhesive/mortar, ensuring 100% coverage beneath the tile to prevent hollow sounds or future cracking. • **Skirting:** Cutting, edge-polishing, and installing matching 4-inch (100mm) high tile skirting flush with or projecting from the wall finished surface, as per the design intent. • **Grouting & Cleaning:** Filling joints with matching epoxy or polymer-modified cementitious grout, followed by a thorough acid-wash and cleaning of the entire floor post-installation. • **Protection:** Applying a protective layer (such as PVC floor protection sheets or POP over plastic sheeting) immediately after curing to prevent scratches or damage from other ongoing interior works (like painting or electrical).	
11	**Proposed Material Specifications (To be approved by Architect)** **Vitrified Tiles:** 2'x2' (600mm x 600mm) double-charged or glazed vitrified tiles (GVT/PGVT). *(Suggested makes: Kajaria, Somany, Nitco, or Rak Ceramics)*. **Tile Adhesive/Mortar:** High-polymer modified cementitious tile adhesive suitable for vitrified tiles. *(Suggested makes: Roff, Laticrete, or Weber)*. **Tile Grout:** Stain-resistant epoxy grout or matching polymer grout with spacers (usually 2mm or 3mm as per design). *(Suggested makes: Laticrete SP-100, Roff)*.	Experienced interior design–cum–renovation agencies specializing in office renovation work and boardrooms.
12	**False Ceiling & Painting Scope of Work**	Experienced interior

	& Material Specifications **False Ceiling: General Scope of Work** • **Framework & Leveling:** Supply and installation of a suspended, Galvanized Iron (GI) framework, securely anchored to the true ceiling using dash fasteners and suspenders, ensuring a perfectly leveled horizontal plane. • **Boarding & Jointing:** Fixing of gypsum boards (or acoustic ceiling tiles) to the framework. For flush ceilings, applying fiber glass tape and jointing compound to all joints, followed by sanding to achieve a seamless, zero-level surface. • **MEP Coordination:** Creating precise, finished cut-outs for all recessed electrical fixtures, HVAC grilles/cassettes, smoke detectors, and fire sprinklers as per the coordinated Reflected Ceiling Plan (RCP). • **Cove Lighting & Details:** Constructing pelmets, edge margins, and hidden coves for LED strip lighting as per the architectural design intent. **False Ceiling: General Scope of Work** • **Framework & Leveling:** Supply and installation of a suspended Galvanized Iron (GI) framework, securely anchored to the true ceiling using dash fasteners and suspenders, ensuring a perfectly leveled horizontal plane. • **Boarding & Jointing:** Fixing of gypsum boards (or acoustic ceiling tiles) to the framework. For flush ceilings, applying fiber glass tape and jointing compound to all joints, followed by sanding to achieve a seamless, zero-level surface. • **MEP Coordination:** Creating precise, finished cut-outs for all recessed electrical fixtures, HVAC grilles/cassettes, smoke detectors,	design–cum–renovation agencies specializing in office renovation work and boardrooms.

	and fire sprinklers as per the coordinated Reflected Ceiling Plan (RCP). • **Cove Lighting & Details:** Constructing pelmets, edge margins, and hidden coves for LED strip lighting as per the architectural design intent. **Painting: Material Specifications (To be approved by Architect)** • **Interior Emulsion:** Premium washable acrylic emulsion with a matte or eggshell finish. *(Suggested makes: Asian Paints Royale, Berger Silk, or Dulux Velvet Touch)*. • **Wall Putty & Primer:** Premium cement-based or acrylic putty and compatible water-based interior primer. *(Suggested makes: Birla White, JK Protomax, or Asian Paints)*. • **Ceiling Paint:** Standard matte interior emulsion (usually bright white) to maximize light reflection.	
13	**Furniture Scope of Work & Specifications** 1. General Scope of Work • **Manufacturing & Supply:** Fabrication, supply, delivery, and professional installation of all modular furniture, custom millwork, and loose seating as per the approved layouts and design intent. • **Site Coordination**: Field measurement of all areas prior to manufacturing to ensure a perfect fit, especially for wall-to-wall credenzas and the reception desk. • **Installation:** Assembly of all workstations, desks, and storage units on-site, ensuring perfect leveling, alignment, and seamless integration with floor boxes and	

electrical/data conduits.

- **Protection & Handover:** Thorough cleaning of all furniture post-installation, removal of packaging debris, and handover with necessary warranty certificates.

2. Proposed Material & Hardware Specifications (To be approved by Architect)

- **Board Material:** BWP (Boiling Water Proof) grade plywood or high-density particle board/MDF for dry areas. strictly BWP marine-grade plywood for the Pantry. *(Suggested makes: Greenply, CenturyPly, or Action TESA).*
- **Finishes**: 1mm thick premium laminate for workstations and storage; high-quality wood veneer with PU polish or back-painted glass for the President and Registrar cabins. *(Suggested makes: Merino, Greenlam, or Royal Touche).*
- **Hardware & Fittings:** Soft-close hinges, telescopic drawer channels, cable managers, and premium handles. *(Suggested makes: Hettich, Hafele, or Blum).*
- **Seating Upholstery:** High-density molded foam with breathable mesh backs for task chairs, and premium leatherette/fabric for executive and waiting lounge seating.

3. Area-Wise Execution Details (Based on Provided Plan)

- **President Cabin (4.3M X 3.1/3.6M)**
  - Desk: One (1) premium executive desk with a side runner/credenza, finished in veneer/premium laminate with wire management.
  - Storage: One (1) full-height or mid-height background storage unit.
  - Seating: One (1) high-back ergonomic executive chair, three (3) premium visitor

chairs opposite the desk, and a lounge seating arrangement (sofa set) for informal meetings.

- **Registrar Cabin (5.58M X 2.8M)**
  - Desk: One (1) executive desk with a side storage runner.
  - Storage: Low-height or mid-height storage credenzas along the wall.
  - Seating: One (1) high-back ergonomic executive chair and two (2) visitor chairs.
- **Cubicles (1.70M X 1.60M & 1.70M X 1.50M)**
  +1
  - Workstations: Two (2) modular L-shaped or straight desks with front modesty panels and fabric/glass privacy screens dividing the space. Each desk to include a 3-drawer mobile pedestal.
    +1
  - Seating: Two (2) ergonomic mesh-back task chairs and two (2) visitor chairs.
    +1
- **Reception**
  - Desk: One (1) custom-designed reception counter with a transaction top, concealed cable management, and adequate under-counter storage (drawers/keyboard tray).
  - Seating: One (1) ergonomic task chair for the receptionist.
- **Waiting Area (5.28M X 2.81M)**
  - Seating: Supply of two (2) multi-seater waiting lounge sofas/benches as indicated in the layout, upholstered in highly durable, stain-resistant commercial fabric or leatherette.
  - Tables: One or two central/side coffee tables to complement the seating.

	• **Pantry (2.20M X 1.457M)** ○ Millwork: Fabrication and installation of under-counter base cabinets (in BWP plywood) and overhead storage units, incorporating space for a sink and microwave. **4. Deliverables from the Agency** • **Shop Drawings: Detailed 2D/3D shop drawings for all custom units (Reception, Executive Desks) prior to production.** • **Material Approvals: Submission of laminate, veneer, and fabric shade cards, along with hardware samples, for the Architect's final sign-off.**	
14		

Renovation agencies will execute the requirements of work, create Shop Drawing and execute renovation of the identified work, in consultation with the institute, ensuring timely completion of the work. The details of the work are given in the table below.

3. Eligibility Criteria:

(A) Applicable for individual above work given in the table above.

Agencies who fulfil the following criteria shall be eligible for submitting their proposals. Joint ventures/Consortium agencies are not allowed to participate and their proposals will not be accepted.

(i) Should be a regular profit making agency.

(ii) Should have satisfactorily completed similar interior designing and renovation works during the period from 01 February 2025 to 01 February 2026 as per details mentioned below. For this purpose, cost of work shall mean gross value of the completed work including cost of material supplied by the Government/client but excluding those supplied free of cost. Three similar completed works each of value not less than Rs. 0.20 Crores
OR
Two similar completed works each of value not less than Rs. 0.6 Crores.

"Similar Work" shall mean:

a) Work/s comprising interior designing and Renovation of Board Room, Reception & Executive Suites etc.

b) At least one completed similar work should have minimum one Board Room/Executive Suites/Reception under one award of work.

c) Should have average Annual Financial Turn Over of Rs. 1.5 Crores and above in respect of Designing & Renovation works completed during 01 February 2025 to 01 February 2026. The financial details duly audited by Chartered Accountants Firm should be submitted. Year(s) in which if there is no turnover shown will also be taken for calculation of average Annual Financial Turn Over.

4. Documents to be submitted in support of eligibility and Qualification.

Agency should submit the following documents with the proposal:-

a) Self-attested copy of the Certificate of registration/incorporation in respect of the applicant organization.

b) Self-attested copies of Telephone bill/Electricity bill/Registered Lease Deed indicating the address evidencing its location in Madhya Pradesh for last two years.

c) Self-attested copies of all valid and applicable licenses for running the business.

d) Self-attested copies of the GST registration certificate, PAN registration.

e) Statement of Annual Turn Over in respect of Designing & Renovation works completed during financial year starting 01 February 2025 to 01 February 2026. Mentioned above, from a registered practicing Chartered Accountant as per Annexure III. Year(s) in which if there is no turnover shown will also be taken for calculation of average Annual Financial Turn Over.

f) RFP document duly signed and official stamp on all the pages to be submitted in original.

5. Validity of the Proposal:

The validity period of the proposal will be 90 days from the last date of submission of proposal documents at MPSDC Indore. A proposal valid for a shorter period may be rejected as non-responsive.

6. Preparation and Submission of Quotations:

a) All entries in the proposal should be legible and filled clearly.

b) Proposal should be typewritten in English and any correction and interlineations in the quotation should be attested with full signature by the Agency. Failing which the quotation will be treated as ineligible. No overwriting will be accepted.

c) All documents/papers should be numbered, signed and official stamped by the Agency on each page.

d) Proposal should be in the sealed envelope and super scribed as Proposal for the "Renovation of Council Office at MPSDC, INDORE".

7. Proposal Submission (STAGE I):
Sealed Proposals should be addressed and submitted along with requisite documents to. Any proposal received online shall be rejected.

8. Late Proposals received:
Quotation submitted or received after the closing date and time will not be considered at all. The Agencies shall ensure that timelines are adhered to and any quotations received later than the specified time and date shall not be entertained.

Other Terms & Conditions

9. General Terms & Conditions:-

(i) The selection of the agencies will be purely based on the merit and fulfilling the eligibility criteria.
(ii) MPSDC, INDORE reserves the right to reject any or all the proposals received, change scope of work for bringing any improvement on the work without assigning any reason.
(iii) MPSDC, INDORE reserve the right to terminate the engagement of agencies for the work process at any stage without assigning any reason to the agencies.
(iv) The participating agencies are requested to compulsory visit the Institute along with the Interior Designer and working on the project, subject to award of the work by the Institute, and get acquainted themselves about the work requirements, specifications and existing building conditions etc. before submitting the proposal.

(v) Any request regarding change of time of submission of proposal may not be considered.
(vi) As per eligibility of the agency the above mentioned can be awarded to either one agency or more than one agencies as per discretion of the Institute.
(vii) The selected agency will be required for completion of the work within the period of work completion only.

10. Evaluation of Proposals (STAGE I):

a) The committee constituted by the competent authority of **MPSDC,Indore** shall evaluate the proposals received with reference to technical requirements and other criteria mentioned in the RFP Document. All eligibility conditions have to be satisfied on the date of submission of proposal and not later.

b) The proposal of the agencies who submit their proposal in the proper format. The proposals of the non-conforming agencies shall be rejected without further evaluation.

c) Any conditional proposal received shall not be considered and will be summarily rejected in very first instance without any recourse to the agency and shall not be evaluated.

d) MPDCI, INDORE may seek such clarification/information/document as may be required for it to satisfy the eligibility of the agencies. Failure on the part of the agency to submit such information within the stipulated time may entail cancellation of the proposal of such agency. MPDCI, INDORE Committee at its own discretion may visit any of the premises of the client(s) as per list provided by the agency and make quality assessment of the services provided, at its own expense.

e)Minimum Qualifying Marks in the Technical Evaluation would be 60 Marks out of 100 Marks.

f) Technical shortlisted agencies shall be required for preparing and submitting BOQ and financial proposal (commercials), in Stage II i.e. Finalization of the agency(ies) for the Work.

g) The metric for evaluation of financial proposal (Stage II) on the scale of 40 marks shall be as follows:

The final selection of the agency for award of work will be based on the score secured in Stage I (Technical evaluation) and Stage II (financial submission) as detailed below: -

(i) The selection of agency will be based on site visit to verify the works executed by the bidder & reference check.

(ii) 60% weightage will be considered for Technical Score (TS) obtained in Technical Evaluation Stage I

(iii) 40% weightage will be considered for the price quoted by the agency in the BOQ i.e. Financial Score (FS) for the work. Financial Score of the proposals will be determined using the following formula:- FS = 100 x (FL/F) Where, 'FS' is the financial score of an agency 'FL' is the lowest Financial Proposal among all and 'F" is the financial proposal of the particular bidder For the purpose of calculation of the Composite Score (CS) for each agency, the weighted shall be 60% for the R=Technical Evaluation (Stage I) and 40% of Financial Score of the respective agency. The Composite Score shall be calculated using the following formula: CS = TS x 0.60 + FS x 0.40 Proposals will be ranked according to the Composite Scores and will be listed in the order of merit as H1, H2 and H3 and so on. The top scores H1 would be eligible for award of work.

11. Evaluation Criteria of the Proposals (Stage I):

(A) Evaluation criteria for evaluation of the agency in respect of Work A or Work B.

S. No	Criterion	Details	Award of Marks (Total 100 Marks)
01	**Technical Manpower:** (Permanent manpower on roll of the agency. Please provide the details for proof). (Annexure-I)	(I) Total 10-15 Nos. (ii) Total 16-25 Nos. (iii) Total 26 and above Nos.	5 marks 7 marks 10 marks Max. 50 marks
02	Conceptualization and Understanding of the works to be delivered at **MPSDC,Indore**. The agency will be required to make a presentation of not more than 30 minutes to the Institute committee on the work.		Max. 50 marks
03	Past experience of successful execution of similar works will be evaluated based on experience of doing similar work and successful completion of projects. (Annexure-II) *	I) Less than 5 similar projects successfully completed (ii) 6-10 similar projects successfully completed (iii) 11 or more similar projects successfully completed	Max. 20 marks
04	**Financial capability of the Agency** Average Annual Financial turnover during last 5 financial years (FY 2021- 22, 2020-21, 2019-20, 2018-19, 2017- 18) Audited balance sheet of the above mentioned financial years is to be submitted. Average Financial turnover shall mean the sum total of the Annual Financial in the relevant financial years divided by 5. (Annexure III)	(i) Average revenue between Rs 0.60 Crores and upto Rs 1 Crore (ii) Average revenue more than Rs 1 Cr and upto Rs 1.5 Crores (iii) Average revenue above Rs 1.5 Cr	Max. 20marks 10 marks 15 marks 20 marks

The participating agencies may please note that for making presentations and/or walk through no reimbursement of expenditure, if any, shall be made by MPSDC, Indore to the agency.

***The selection of agency will be based on site visit to verify the works executed by the bidder & reference check.**

12. EMD (Earnest Money Deposit) (Stage II):

The shortlisted agency(ies) in Stage for Stage II (i.e. submission of BOQ and financials) shall be required to submit an EMD amounting to Rs. 2,50,000/-, and is to be paid through a Demand Draft in favour of "M.P. State Dental Council", payable at Indore. The DD has to be attached with the BOQ and financials submission, without which the proposal would not be considered valid. The EMD shall be refunded to unsuccessful.

13. Award of Work:

a. **MPSDC, Indore** will award the work to the successful agency(ies) and issue "Letter of Award" that shall prescribe the terms of payment to the agency(ies) in consideration of the execution of work/services by the agency.

b. The successful agency(ies) will be required to complete the Works within the agreed duration. Any request for extra time will not be considered at any cost by **MPSDC, Indore.**

c. Failure of the successful agencies to comply with the requirements of the above clauses shall constitute sufficient grounds for the annulment of the award and forfeiture of bid security.

14. This document constitutes no form of commitment on the part of **MPSDC, Indore** Furthermore, this document confers neither the right nor an expectation on any agency to participate in the selection process.

15. When any proposal is submitted pursuant to this RFP, it shall be presumed by **MPSDC, Indore** that the agency has fully ascertained and ensured about its eligibility to render services, in the event of the same being selected ultimately to act as such, under the respective governing laws and regulatory regime and that there is no statutory or regulatory prohibition or impediment to acting such Service Provider and it has the necessary approvals and permissions and further suffers no disability in law or otherwise to act as such.

16. MPSDC, Indore reserves the right to vary/alter/amend the eligibility criteria at any time, in its discretion, before the last date of submission of proposals.

17. The selected agency(ies) shall comply with and abide by such directions that **MPSDC, Indore** may issue from time to time.

18. The proposal and all correspondence and documents shall be written in English. All proposals and accompanying documents received within the stipulated time shall become the property of **MPSDC, Indore.**

19. Any matter relating to the appointment of selected agency for the wok(s) shall be governed by the Laws of Union of India and State of Madhya Pradesh from time to time. Disputes, if any, shall be subject to exclusive jurisdiction of courts at Indore.

05/03/26.

(Registrar)
M.P. State Dental Council
Indore

REGISTRAR
M.P. STATE DENTAL COUNCIL
INDORE (M.P.)